



DJ BASIN, WELD, COLORADO

NOVEMBER 16, 2016

BHA- 3.75" Mill, 2.875" PDM, .75 AV Sub, 2.875" CT Strider 4 BPM, Hydraulic Disconnect, 2.375" Connector

2.375" Coil Tubing, 4.5" 13.5 lb. Casing

6,138' TVD 14,034' PBTD

Drill-out

SPDI was called out to deliver a 2.875" CT Strider set at 4 BPM to drill-out the remaining 8 plugs that the competition was unable to complete. By implementing the correctly configured CT Strider, we were able to maximize the thrust force given the operator's targeted flow rates. The CT Strider drilled the remaining 8 plugs and finished the job!