

CT STRIDER



POWDER RIVER BASIN, CAMPBELL, WYOMING

JANUARY 11,

2017

BHA- 4.767 Mill, XO, 4 BPM PDM, 3.125" CT Strider 4 BPM, Hydraulic Disconnect, Check Valve, XO, 2.375" Connector

2.375" Coil Tubing, 5.5" 17 lb. Casing

6,867' KOP 15,230' PBTD

Clean-out

The CT Strider completed another clean-out run in Campbell County, WY. From start to finish (KOP to PBTD), it only took 98 minutes to complete the job. The CT Strider produced a RIH rate of 77 ft./min while generating 10K lbs. of working weight at PBTD!